

# Company Standard - 38kV MV & LV Civil & Ducting Standard

#### **Governance and Control**

Issuing Authority:	Head of Asset Management
Content Owner:	Underground Networks Section Asset Management
Document is Effective from:	24/01/2017
Document Number:	DOC-090217-CMY

This document shall be complied with by all end users. Feedback on its content is welcome and should be given to the Content Owner. Should a derogation from any part be required, this shall be referred to the Issuing Authority. Derogations shall be approved by the Issuing Authority only.

# Contents

Section	1 – Overview	1
Inti	roduction	1
Sco	ppe	1
Ma	Indatory References	1
Section	2 – Provisions	2
1.	General	2
2.	Materials Requirements	2
3.	38kV Ducting Standards	3
4.	MV Ducting Standards	4
5.	LV Ducting Standards	4
6.	Duct Proving	4
7.	Duct Sealing & Duct roping	6
8.	Quality Conformance	6
Annex A	A. (Mandatory or Informative)	7
A.1	38kV Single Circuit Trench Cross-section 5 duct way	7
A.2	2. 38kV Single Circuit Trench Cross-section 4 duct way	8
A.3	3. 38kV Single Circuit no Communication Duct	9
A.4	l. 38kV Double Circuit Trench Cross-section 8 duct way	10
A.5	38kV, MV Screen Sectionalising Chamber, Comms Chamber & Lubrication point	11
A.6	5. 38kV Drain Crossing Under	13
A.7	7. 38kV Culvert Crossing	14
A.8	38kV Drain Crossing Over	15
A.9	). 38kV Joint Bay Drawing	16
A.1	.0. 38kV Joint Bay Backfill	17
A.1	1. 38kV Ducting at Mast & Pole Set	18
A.1	2. MV Trench Cross Section	19
A.1	3. MV Joint Bay	24
A.1	.4. MV Joint Bay Backfill	25
A.1	.5. MV Ducting at Pole	26
A.1	.6. Ducting within Station Compound	27
A.1	7. Thermal Backfill Grading Curve	28
A.1	.8. Ducting & Civil Inspection Report	29
A.1	.9. Duct Inspection Report	31
A.2	20. Duct Proving Report	32
Docume	ent Control	34
Definition	ons and Abbreviations	35

# Section 1 – Overview

#### Introduction

It is ESB Networks Policy to use a fully ducted system for Underground Networks installations. Ducted systems, when installed to a high standard show a reduced fault rate relative to direct buried systems and provide greater protection against external interference. In addition ducted installations allow the flexibility to change cable size and type, install spare ducts, and provide a means of removing defective cable without the high costs of excavation and reinstatement.

Please refer to the "Document(s) Superseded" section to see the list of documents cancelled in whole or part by this Procedure.

#### LIFETIME PERFORMANCE STANDARD FOR DUCTED SYSTEMS

The expected lifetime standard for ducted trenches is 80-100 years minimum. It is vital for the serviceability and maintainability of the assets that specified minimum clearance and depth standards are maintained and that mechanical strength, thermal surround and quality of ducts and protective materials all meet ESB Specification standards.

Effective quality control measures shall be in place to ensure that minimum ESB Networks standards for design, construction and materials are complied with. A duct installation installed in accordance with ESB Networks standards will provide a safer system.



CAUTION: Substandard ducted installations shall not be accepted.

#### Scope

This Standard details the design and construction requirements for ESBN 38kV MV & LV Ducting and Civil installations for Underground Networks including Stations.

## **Mandatory References**

The following documents, in whole or in part, are indispensable for the application of this document. For dated references, only the edition stated applies. For undated references, the latest edition of the referenced document (including any alerts which amend the document) applies;

- MV & LV Ducting Summary <u>DTIS-230908-BUV</u>
- MV & LV Cable Installation Standards and Practices Manual DOC-240205-AJC
- Housing Schemes Guidebook for ESB Networks Standards for Electrical Services <u>DTIS-050500-AZF</u>
- ESB Networks Approved Material Suppliers <u>DOC-200815-CAP</u>
- <u>ESBN Specification Number 16113</u> Plastic Ducts and Fittings for Power and Telecommunications Cables
- <u>ESBN Specification Number 16001</u> Plastic Warning & Protection Tape Strips Tiles & Concrete Marker Posts for HV, MV & LV Cables & Plastic Covers for LV Earth Guards
- ESBN Specification Number 16002 Plastic Cable Ties

## Section 2 – Provisions

#### 1. General

Design considerations at planning stage shall be given to safety, environmental impact and long term Asset Lifetime.

Prior to duct installation the ducting contractor and all associated subcontractors shall attend an ESB Networks ducting workshop and proof of attendance shall be provided to ESB Networks.

Joint Bays shall be installed where joints are required in a circuit or where pulling points are required in a circuit. Joint Bay drawings are detailed for 38kV in <u>Annex 9</u>, for MV in <u>Annex 13</u>.

C2 Communication Chambers shall be installed at each joint bay for 38kV to facilitate communication fibre installation. See Annex 5 for details.

On cable runs in excess of 2 km cable screen sectionalising shall be designed for 38kV and MV. See Annex 5 for details.

Screen sectionalising chambers shall be installed at every alternative joint bay to facilitate this. See <u>Annex 5</u> for details.

Where non-standard depth is unavoidable in some situations or where non-standard design is unavoidable, Asset Management Underground Networks Section shall be consulted. Consideration should be taken into account for the location of Joint Bays and C2 chambers regarding safe future access.

Compaction of Material in which ducts are laid shall be sufficiently compacted to prevent the occurrence of residual consolidation leading to trench surface depression, trip and falling hazards and ultimately reinstatement failure. Local Authority and NRA requirements shall be adhered to for finish reinstatement.

The minimum clearance of 300mm from other services and 600mm from high pressure gas or water mains shall be strictly observed. Deviations from this over short distances at unavoidable "Pinch Points" may be acceptable in some situations — for these situations where non-standard design is unavoidable Asset Management Underground Networks Section shall be consulted and a Design Risk Assessment produced.

Local ground conditions shall be taken into account for design as this will directly affect approach taken to installations.

## 2. Materials Requirements

All materials used for duct & joint bay installation shall be approved by ESBN on the Approved suppliers website link below,

https://www.esbnetworks.ie/tns/publications/-in-category/categories/publications/underground-networks-technical-documents/approved-suppliers



ESBN will not accept ducting installations where materials used are not sourced from the Approved suppliers list.

The bedding sand to be used around electric cables ducts & Joint bays shall be natural unwashed sand in accordance with BS EN 12620. The grading, when determined in accordance with BS EN 933-1, Section 103.1, shall comply with grading limit C in Table below and the grading curve shown in Annex 17. It is desirable that the sand shall have a maximum resistivity of 1.0 Km/watt at 0% moisture content. The sand shall be compacted so that no residual consolidation will occur.

Pea gravel is unacceptable as it significantly reduces cable current carrying capacity.

BS882 Sieve Size	3/16"	1/8"	7	14	25	52	100
% Passing by Weight	95	89	84	75	54	18	1.6



All installers of ducting should be made aware of this requirement including developers and ducting contractors. The grading curve or that shown in <u>Annex 17</u> shall be issued with ducting installation contract documentation.

#### **Lean Mix Concrete Specification and Compaction**

Cement bound material shall be to Cl.1038 or Cl.1039 for lean mix concrete and shall be compacted in layers not exceeding 150mm and in accordance with Cl.813.10 and Table 8/4 of N.R.A Specification for Roadworks Series 800. Cube testing and Thermal testing shall be carried out on samples and locations where samples were taken be recorded on as builds. Foamed concrete shall not be accepted as it reduces cable ratings.



Red dye for Lean mix surround shall be used where proximity to privately owned cable circuits will be a factor, for these situations Asset Management Underground Networks Section shall be consulted.

#### **Granular Material Specification and Compaction**

Granular material for trench reinstatement shall be to Cl.804 (which is Granular Material Type B or Cl.806 wet-mix macadam and exceeding 150mm and in accordance with Cl.813.10 and Table 8/4 of N.R.A Specification for Roadworks Series 800.

Joint Bay backfill is detailed in

Annex 10 for 38kV Joint bays

Annex 14 for MV Joint bays.

## 3. 38kV Ducting Standards

38kV Ducting

38kV Duct Size	Duct Type	Duct Length
Standard Lay 110mm SDR 17.9	HDPE	6 / 9/ 12 Mtr
Directional Drill 110mm SDR 11 / 14.7	HDPE	Coils
110 mm Coupler	HDPE	250mm

• For Station compound duct type refer to Annex 16

For detailed 38kV trench cross sections refer to

Annex 1 for Single Circuit 5 duct way

Annex 2 for Single Circuit 4 duct way

Annex 3 for Single 3 duct way

Annex 4 Double Circuit 5 duct way

For detailed trench cross section at Pole / Mast refer to

Annex 11 38kV Ducting at Mast & Pole Set

For detailed 38kV non-standard trench cross sections refer to:

Annex 6 for typical crossing under a drain

Annex 7 for typical Culvert crossing

Annex 8 for typical crossing over a drain

## 4. MV Ducting Standards

#### **MV** Ducting

MV Duct Size	Duct Type	Duct Length
125mm uPVC	uPVC	6 Mtr Lengths
160mm uPVC	uPVC	6 Mtr Lengths

• For Station compound duct type refer to <u>Annex 16</u>

For detailed trench cross section refer to <u>Annex 12</u>
For detailed trench cross section at Pole refer to <u>Annex 15</u>



125mm uPVC duct size shall be used wherever possible, as required by environmental and sustainability legislation, as magnetic field emissions and cable screen currents and kwh losses are reduced due to the more trefoil cable formation in the 125mm duct.

## 5. LV Ducting Standards

#### LV Ducting


LV Duct Size	Duct Type	Duct Length
125mm uPVC	uPVC	6 Mtr Lengths

For detailed trench cross section refer to Annex 12

#### 6. Duct Proving

After duct installation, compaction of the surround materials and pre roping with 12mm rope, the ducts shall be cleaned, proven and pre lubricated the ducts to ensure that no foreign matter including water remains inside the duct circuit. Pre-lubrication is carried out at a rate of 10 litres per 100mtrs of ducting.

The ducts shall be brushed, proven and cleaned using a brush, mandrel and sponge in that order in the duct.



Sizes for each item are detailed in table below.

Duct Size		Duct Type	Mandrel Size	Brush Size	Sponge Size
OD mm	ID mm		OD (mm)	OD(mm)	OD (mm)
110mm	97mm	HDPE	90	120	110
110mm	90mm	Directional Drill HDPE	85	110	95
125mm	117mm	uPVC rigid	105	130	120
125mm	111mm	HDPE	105	130	120
125mm	107mm	Directional Drill HDPE	102	130	110
160mm	152mm	uPVC rigid	135	170	155
160mm	141mm	HDPE	135	160	155
200mm	177mm	HDPE	165	210	187
250mm	221mm	HDPE	210	260	230

Duct proving printouts and signed test certificates are required prior to cable installation. If the duct seals have been disturbed or a delayed period of time between duct installation proving and cable installation re proving will be required for the duct circuit.

The direction of the cleaning and proving shall be the same as that of the planned cable pulling. Cleaning and proving shall be carried out using a winch which has a calibrated dynamometer and printout. The dynamometer shall be calibrated annually and certified by an independent calibration tester. The certification shall be provided to the Employer before any cleaning or proving commences. Pulling tension shall not exceed 1 tonne (10 kN).

Results of cleaning and proving of the ducts shall be recorded on the Ducting Cleaning/Proving Report by the crew that carried out the process, this Report can be found in <u>Annex 20</u>. The report shall be agreed and signed by the ESBN representative who witnessed the entire suite of cleaning and proving operations. Fully completed reports and print outs for each section of ducting shall be submitted to the ESBN for review.



**CAUTION:** The proving of the ducts shall be deemed failed if the following conditions are not made. Cable shall not be installed if this occurs.

- The pulling tension exceeds 1 tonne (10 kN)
- The mandrel is stuck
- The mandrel is moving with sudden bursts even if the pulling tension is less than the maximum 1 tonne permitted
- The rope shoots suddenly up the duct
- The ducts do not maintain the same formation as at the start of the pull

Note: If this situation occurs Asset Management Underground Networks Section shall be consulted.

## 7. Duct Sealing & Duct roping

Following successful duct proving process, the following shall be carried out

- Ducts pre roped, the required rope size is 12mm. This shall be in one continuous length
  where possible if the ropes require splicing they shall be spliced using the ESBN approved
  method
- Water sealing rubber bungs shall be fitted to prevent water, sand or other debris getting into them. Refer to table below for duct sealing codes and details.

Duct	Sealing Bag	Code
110mm – 125mm	TYCO Bag 125mm (10 per box) Suitable for 110mm	9317599
	&125mm Duct	
150mm – 200mm	TYCO Bag 150mm (10 per box) Suitable for 160mm	9317596
	&200mm Duct	
200mm	TYCO Duct Reducer – Required for 200mm Ducts (4 per	9317601
	box)	
All	Inflation Tool	9317597
All	CO <sub>2</sub> Canisters	9317600

## 8. Quality Conformance

Quality conformance for duct installation shall be implemented at the beginning during the installation and when the installation has been completed.


For Civil Inspection report refer to <u>Annex 18</u>
For Duct Inspection report refer to <u>Annex 19</u>




CAUTION: Substandard ducted installations shall not be accepted.

## Annex A. (Mandatory or Informative)

#### A.1. 38kV Single Circuit Trench Cross-section 5 duct way



#### A.2. 38kV Single Circuit Trench Cross-section 4 duct way




A=110 mm Outer Diameter HDPE ESB Approved Duct, SDR=17.6, ESB Code: 9317556


All Dimensions in Millimetres

#### Note:


The Contractor shall provide test certificates confirming that the thermal resistivity of CBGM B is maximum 1 K.m/W.




#### A.3. 38kV Single Circuit no Communication Duct



#### A.4. 38kV Double Circuit Trench Cross-section 8 duct way



#### 38kV, MV Screen Sectionalising Chamber, Comms Chamber & Lubrication point A.5.




PRECAST CONCRETE NOTES:

- ALL PRECAST CONCRETE ELEMENTS TO BE MANUFACTURED TO B.S. EN 13369:2013 "COMMON RULES FOR PRECAST CONCRETE PRODUCTS"
- LIFTING INSERTS TO BE DESIGNED & INSTALLED TO PD CEN/TR 15728:2008 "DESIGN AND USE OF INSERTS FOR LIFTING AND HANDLING OF PRECAST CONCRETE ELEMENTS".
- 3. WEIGHT OF PRECAST CONCRETE UNIT = 2.2 T. SPECIFIED LIFTING INSERTS HAVE A S.W.L. OF 4 T. ACCOUNTING FOR DYNAMIC LOADING.
- 4. LOCATION & SPECIFICATION OF LIFTING INSERTS ARE ASSUMED TO FACILITATE DEMOULDING AND HANDLING IN PRECAST MANUFACTURING FACTORY. IT IS THE RESPONSIBILITY OF THE PRECAST MANUFACTURER TO NOTIFY THE ESIB ENGINEER IF THESE ARE UNSUITABLE FOR HIS MANUFACTURING METHODOLOGY, ESBI ENGINEER TO BE INFORMED OF ANY ALTERNATIVE LIFTING LOCATIONS FOR FACTORY HANDLING & DEMOULDING.
- 5. CONCRETE TO HAVE A MINIMUM STRENGTH OF 30 N/mm2 PRIOR TO HANDLING OR DEMOULDING.
- MAIN CONTRACTOR TO ENSURE THAT A METHOD STATEMENT AND RISK ASSESSMENT INCLUDING A LIFTING PLAN, ARE PRODUCED FOR INSTALLATION AND ARE AVAILABLE TO ESH DISGNEED FOR REVIEW IF REQUESTED. LIFTING PLAN TO INCORPORATE REQUIREMENTS OF LIFTING INSERTS AND LIFTING LOOP FYES.
- 7. A MINIMUM LIFTING SLING ANGLE OF 60' TO THE HORIZONTAL IS REQUIRED.
- 8. A LIFTING SYSTEM WHICH ENSURES ALL LIFTING POINTS TAKE ON AN EQUAL LOAD IS REQUIRED.
- 9. TRANSPORT THE CHAMBER BY TRAILER WHEN TRAVELLING OVER ROUGH TERRAIN TO AVOID DAMAGE TO LIFTING ANCHORS.
- HALFEN DEHA SPHERICAL LIFTING ANCHORS TO BE USED AS SPECIFIED. ANY DEVIATION FROM THIS MUST BE NOTIFIED TO ESBI ENGINEER BY PRECAST MANUFACTURER.
- 11. FORMWORK FOR PRECASTING TO BE OF A MINIMUM STANDARD OF VARNISHED WOODEN MOULD WITH PLANED BOARDS.
- 12. CONCRETE TO BE GRADE C32/40, AS SPECIFIED IN TABLE 1


ELEMENT	BLINDING & MASS CONCRETE, DRAINAGE PIPE & MANHOLE SURROUNDS.	GROUND BEAMS, FOUNDATIONS & PITS CHAMBERS		
EXPOSURE CLASS	X0	XC4		
MIN. BINDER (CEMENT+GGBS) CONTENT (kg/m²)	220	320		
GGBS TO EN 15167-1 (kg/m²)	0	95		
CEM II / A-L TO I.S. EN 197-1 (kg/m²)	220	225		
MAX. WATER/CEMENT RATIO	-	0.50		
CHLORIDE CONTENT CLASS	Cl. 1.0	CI. 0.40		
MAX. AGGREGATE (mm)	10	20		
MIN. COVER (CMin) (mm)	-	40		
*COMPRESSIVE STRENGTH CLASS C16/20 C32/40 @ 28 DAYS.				



- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S, ARCHITECT'S AND ESB NETWORKS DRAWINGS & SPECIFICATIONS.
- 3. DO NOT SCALE DIMENSIONS.
- THE CONTRACTOR SHALL CHECK ALL DIMENSIONS PRIOR TO CONSTRUCTION, ANY DISCREPANCIES TO BE NOTIFIED TO THIS OFFICE IN WRITING IMMEDIATELY.
- TEMPORARY SUPPORTS TO THE SIDES OF THE EXCAVATION MAY BE REQUIRED DEPENDENT ON SUBSOIL, METHOD OF WORK AND SITE CONSTRAINTS, AND ARE TO BE AGREED WITH THE ESBI ENGINEER PRICE TO COMMENCEMENT OF EXCAVATION. SIDE SLOPES OF AN UNSUPPORTED EXCAVATION DEPENDENT UPON SUBSOIL, AND SHALL BE AGREED WITH ESBI ENGINEER.
- MAIN CONTRACTOR TO PROVIDE A METHOD STATEMENT AND RISK ASSESSMENT FOR THE EXCAVATION WORKS FOR THE ESBI ENGINEER TO REVIEW.
- 7. THE CONSTRUCTION, AS SHOWN, IS APPLICABLE ONLY WHERE THE SUBSOIL AT FORMATION LEVEL EXCEEDS 100  $kN/m^2$  BEARING CAPACITY.
- SUITABILITY OF THE COVER AND CHAMBER TO BE ASSESSED BY THE PROJECT ENGINEER IN CIRCUMSTANCES OF HIGH TRAFFIC LOADING IN ACCORDANCE WITH THE RECOMMENDATIONS OF NRA DESIGN MANUAL FOR ROADS AND BRIDGES ADDENDUM TO HA 104/09.
- 9. COVER AND FRAME TO B.S. EN 124.
- 10. COVER SHALL HAVE APPROVED BADGED MARKING INCORPORATED TO THE APPROVAL OF THE ESBI ENGINEER.
- 11. ALL MATERIALS AND WORKMANSHIP TO BE IN ACCORDANCE WITH THE NRA SPECIFICATION FOR ROADWORKS




[LIFTING EYE DETAIL - IN WALL]




	Chamber Dimensions	
Height	1300 mm	
Width	933 mm	
Length	1205 mm	


#### A.6. 38kV Drain Crossing Under




#### A.7. 38kV Culvert Crossing




#### A.8. 38kV Drain Crossing Over




#### A.9. 38kV Joint Bay Drawing








### A.10. 38kV Joint Bay Backfill




#### A.11. 38kV Ducting at Mast & Pole Set










#### A.12. MV Trench Cross Section






Copyright © 2016 ESB









# A.13. MV Joint Bay


	MV Joint Bay Dimensions
Height	1000 mm
Length	2900 mm
Width	1600 mm





## A.14. MV Joint Bay Backfill




#### A.15. MV Ducting at Pole








## A.16. Ducting within Station Compound



Duct Size	Material	Voltage	Usage
125mm	HDPE	110kV	All 110kV works
125mm*	uPVC	MV	All MV works.  *Can be used in station compound s for MV side of Transformers once short runs are used.  *Can be used for 38kV side of Transformer once short runs are used and within a station compound.
110mm	HDPE	38kV	All 38kV works
110mm	uPVC		Bends Only for 38kV arm chair

NB: 1 cable per duct (3 Ducts per circuit) all above construction is within station compound ONLY

## A.17. Thermal Backfill Grading Curve



# A.18. Ducting & Civil Inspection Report



# **Ducting & Civil Inspection Report**

Site Details:	_
Date:	
Detail of ducting being installed:	

#### **Duct Installation**

		Comment	<u>Y/N</u>
1.	Are all ducts, couplers and preformed bends		
	stored correctly on site		
2.	Have the ducts the ESBN specified marking		
3.	Are transport caps fitted to all ducts		
4.	Have the duct installation crew a specification		
	drawing		
5.	Have the duct installation crew completed the		
	ESBN ducting workshop		
6.	Are duct position & levels being recorded as		
	laid		
7.	Are the correct tools on site for correct duct		
	installation		
	Ducting Template		
	Wacker plate ( Mechanical Compactor)		
	Cable Ties		
	Lubrication for coupler installation		
8.	Are all the materials used ESBN approved		
9.	Is the trench the standard width and depth as		
	per specification drawing		
10.	Is the CBGM B / ESBN approved sand base		
	layer compacted		
11.	Are the power ducts laid in to ESBN		
	specification with correct formation and		
	spacing		
	Transport caps fitted until duct engagement		
	with coupler		
	Trefoil ducting are ducts cable tied every 3		
	Mtrs		
	Are couplers staggered		

Is lubrication being used on couplers	
Is a rubber mallet being used to tap couplers in	
to position on the duct / uPVC to tap spigot	
into socket	
Is the template being used	
12. For uPVC bends is the bend supported	
according to ESBN minimum standard	
13. Is the CBGM B / ESBN approved sand layer	
compacted over the power ducts	
14. Is the red warning strip laid in at the standard	
depth and position over the ducting	
15. Are the fibre ducts laid in to ESBN	
specification with correct formation and	
spacing Transport caps fitted until dust angagement	+
Transport caps fitted until duct engagement with coupler	
Is lubrication being used on couplers	+
Is a rubber mallet being used to tap couplers in	+
to position on the duct	
Is the template being used	+
16. Is the CBGM B / ESBN approved sand layer	+
compacted over & around the fibre ducts	
17. Is the red warning strip laid in at the standard	+
depth and position over the ducting	
18. Is the specified backfill used for filling the	
remainder of the trench	
19. Is the yellow warning tape installed to	
standard depth and position in the trench max	
300mm from finished ground level	
20. Are ESBN approved duct seals used when	
ducting is installed	
21. When the ducting circuit is completed is the	
correct backfill around the ducting and duct	
route accurately recorded	
22. Has photographic evidence of installation been	
recorded	

 Comments from Duct Installation:	

# A.19. Duct Inspection Report



**Duct Inspection Report** 

		Comment
1.	Project Name and Worksite	
2.	Date of Delivery to site	
3.	Date and Location of Inspection	
4.	Name of Duct / Coupler Supplier	
5.	Duct Size ( 110, 125, 160, 200, 250mm)	
6.	Duct Type (uPVC / HDPE)	
7.	Wall thickness	
8.	Duct Length	
9.	Quantity of Ducts	
10.	Quantity of Couplers	
11.	Are Ducts & Couplers Packaged and Secured	
	( Timber struts 3 & Nylon or Plastic Straps)	
12.	Are ducts marked with ESBN Approved Specification No. 16113 marking?	
13.	Are Ducts discoloured?	
14.	Are all ducts fitted with Transportation Caps?	
15.	Are there any visible signs of Damage along lengths of Ducts?	
16.	Are there any visible signs of Damage to ends of Ducts?	
17.	Are duct end chamfered inside and outside?	
18.	Are there any visible signs of damage to couplers?	
19.	Are rubber seals correctly fitted to all Couplers?	
20.	Any others items of Note?	

Signed & Dated	

# A.20. Duct Proving Report



## **ESB Networks**

Ducts	Clea	ning/	Prο\	/ing	Reno	rt
Ducts	CICa	iiiiig/	1101	/IIIg	INCHO	יוע

Project:				
Duct ID	Duct Diameter(s) (mm)	Sponge Diameter (mm)	Brush Diameter (mm)	Mandrel Diameter (mm)
	al No		date	
DII	ection of proving from		to	
Typical o	circuit cross section &	Ducts formation & start of the pull	ID at the Ducts	formation & ID at the end of pull
e-Taking	Over			

Duct ID	Duct Designation	Max Pulling Tension (tonnes)	Comments
1			
2			
3			
4			
5			

Have the ducts maintained the correct for	rmation?	Yes 🗌	No
Rubber bungs fitted after ducts proving?		Yes 🗌	No
Have the ducts been cleaned and proved	successfully?	Yes 🗌	No
Signed for Contractor:		_	
Name of Contractor:	signature		date
ESB Supervisor who witnessed the tests:		_	data
	signature		date
CAUTION: The proving of the du made:	cts shall be deemed as failed if the follow	ing conditio	ns are not

- The pulling tension exceeds 1 tonne (10 kN)
- Mandrel is stuck
- Mandrel is moving with sudden bursts even if the pulling tension is less than maximum specified
- Rope shoots suddenly up the duct
- Ducts do not maintain the same formation as at the start of the pull

# **Document Control**

# **Policy Base**

Policy No.	Policy Title

### **Document Control**

Version	Date	Details	Originator	Revision Class	Section Update
0.1	24/01/2017	Original	Asset Management		

#### **Document Review**

Role	Name	Date	

# **Document Approval**

Role	Name	Date

# Document(s) Superseded

Document No.	Title	Full (F) / Partial (P)
DOC-240205-AJC	Summary of the MV LV Cable Installation Standards and Practices Manual	Р
DOC-230908-ATU	DOC-230908-ATU Summary of MV&LV cable Installation Standards & Practices Manual	

#### **Distribution List**

This document is for circulation to personnel who undertake the following activities;

x A	All ESB Networks Staff		All Contractors		
		Contractor Management Design Services Fibre optic on the Network Finance Fleet Management Legal Material Services Operations Overhead Networks (HV) Overhead Networks (MV/LV) Procurement Substations (HV) Substations (MV/LV) Technical Training Telecom Services Underground Networks (MV/LV) Work at the Meter	x \[ \] \[ \] \[ \] \[ \] \[ \] \[ \] \[ \] \[ \] \[ \] \[ \]  Others	Civil Haulage Overhead Lines Substations Timber Underground Networks (specify)	

# **Definitions and Abbreviations**

## **Definitions**

CBGM B: Cement Bound Granular Material Category B

CL : Clause

CO<sup>2</sup>: Carbon Dioxide

HDPE: High Density Polyethylene

kN: kilo Newton

K.m/W : Kelvin Meter per Watt

LV : Low Voltage mm : millimetres MV : Medium Voltage

N: Newton

N.R.A: National Roads Authority uPVC: Unplasticized Polyvinyl Chloride

38kV: 38,000 Volts

### **Terminology**

For the purposes of this document, the following terminology applies;

Shall Designates a company requirement where conformance is mandatory.

Should Designates a company recommendation where conformance is recognised as best practice.

May Designates a Permissive Statement - an option that is neither mandatory nor specifically recommended.



CAUTION: Used to give the end user information on what can happen, why and the consequences of ignoring the caution.



Used to give the end user specific, important information to help complete the task or procedure correctly.



This is a stop or critical point in the procedure. It contains a rule that shall be followed by the end user.